DEPARTMENT OF AGRICULTURE.

Notification dated Bangalore, 27th August 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, Bangalore, up to 2 P.M. on Saturday the *15th September* 1928, for constructing the Head Master's Quarters at Ramakrishnapur, Anekal Taluk.

2. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed in four weeks from the date of intimation of acceptance of the tender.

3. Tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed :—

Description of work	Unit	Rate

4. Each tender must be accompanied by a deposit of Rs. 100 in cash as earnest money and be superscribed " Tender for constructing Head Master's Quarters at Ramakrishnapur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Agricultural Engineer, subject to approval by the Director.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond in default of which tender will be considered cancelled and his earnest money will be forfeited.

7. Earnest money of rejected tenderers will be returned.

8. The quotations should be noted in words as well as in figures.

No.	Description of work	Unit	Quantity
1	Earthwork excavation for foundations...	C.yds.	30
2	Stone in mud	C.ft.	1,088
3	Brick in mud	„	1,454
4	Brick in mortar	„	409
5	Stone slabs 4" thick	„	296
6	Teak wood doors	„	182
7	Teak wood windows—big with iron bars complete ...	S.ft.	48
8	Teak wood windows—small with iron bars complete ...	„	41
9	Teak wood wrought and put up	C.ft.	57·73
10	Roofiing with Mangalore tiles on teak reepers	Sqr.	12·75
11	Ridge tiles set in mortar	R.ft.	27½
12	Flooring with Cuddapah slabs	Qrs.	6·75
13	Pillar post with base stone and capital	Each	1
14	Plastering with mortar 2 coats	Sqr.	36·53
15	Pointing with mortar	„	1·3
16	Chocolate painting to doors and windows	„	6·8
17	Wood-oiling for wood work	„	5·54
18	White washing—2 coats	„	25·28
19	Colour washing	„	11·25
20	Filling with earth available from excavation	C.yd.	25
21	Mortar bond	R.ft.	96
22	Cornice	„	34
23	Constructing a latrine	L. S.	...

M. G. SINGRACHAR,
Agricultural Engineer.